CHITALDRUG DIVISION.

Dated 8th July 1907.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Chitaldrug Division, up to 27th July 1907, for restoring Siddapur Anikat and Channel in Molakalmuru Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1909.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Chitaldrug between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 1,000 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Siddapur Anikat and Channel in Molakalmuru Taluk;" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate for restoring Siddapur Anikat and Channel in Molakalmuru Taluk, Chitaldrug Division.

Items of work.	*Per*	*Quantity.*
Anikats		
1. Concrete with surki mortar	C. ft.	935
2. Stepping rock	Sq. ft.	969
3. Cutting holes 6″×6″×6″ in hard rock	No.	73
4. Pin stones 1½′×6″×6″ complete	Each	73
5. Burnt stone slabs	S. ft.	1,869
6. Do. in surki mortar	C. ft.	1,920
7. Pointing with do	Sqr.	26·39
8. Rough pointing	Do	86·40
9. Dismantling brick work	C. ft.	180
10. Burnt brick in surki mortar	Do	300
11. Plastering with surki mortar	Sqr.	5·00
12. Bailing water and removing sand	L. S.	...
13. Burnt stone wall	C. yd.	90
14. Repairing the rear slope of No. IV anikat and burnt stone wall, etc.	L. S.	...
Closing up the breach with a masonry wall and opening out a deviation channel.		
1. Stepping rock	S. ft.	4,970
2. Burnt brick in surki mortar	C. ft.	14,611
3. Plastering with surki mortar	Sqr.	104·02
4. Burnt stone slabs	S. ft.	2,404
5. Do Roughly dressed	Do	1,421
6. Boring holes in rock	Each	165
7. Pin stones 1½′×5½″×5½″	Do	165
8. Surki concrete	C. ft.	1,527
9. Earthwork, channel excavation	C. yd.	4,341
10. Burnt stone revetment	Do	349
11. Excavating trial pits to find out the exact channel line	L. S.	...
12. Compensation for land where the new deviation channel is to be excavated	Do	...

Items of work.	*Per*	*Quantity.*
Constructing a scouring sluice of two vents 3′×5′.		
13. Stepping rock	S. ft.	46
14. Burnt brick in surki mortar	C. ft.	229
15. Burnt stone slabs	S. ft.	50
16. Plastering with surki mortar	Sqr.	1·83
17. Groove stones	No.	4
18. Teakwood shutters (complete)	No.	2
Head sluice.		
1. Removing sand	C. yd.	119
2. Stepping or benching rock	S. ft.	415
3. Removing loose or embedded boulders...	L. S.	...
4. Surki concrete	C. ft.	207
5. Burnt stone in surki mortar	Do	3,942
6. Burnt stone slabs	S. ft.	645
7. Pointing with surki mortar	Sqr.	20·65
8. Groove stones	Each	6
9. Teakwood shutters complete with iron works each 2′ × 10½″ × 3′ —3″ × 3″	Do	3
10. Gear 7′ high complete with nuts and bolts	Do	3
11. Teakwood beam	C. ft.	20
12. Tarring the shutters and teak beam and oiling the gear ...	L. S.	...
13. Bailing water	Do	...
14. Dismantling	Do	...
Right flank bund.		
15. Removing sand	C. yd.	1,232
16. Do block slushy earth or silt mixed with water ...	Do	350
17. Do silt	Do	94
18. Earthwork foundation to revetment	Do	264
19. Do to bund lead 50 yards with watering and tamping ...	Do	2,490
20. New burnt stone work	Do	401
21. Turfing	S. yd.	931
22. Grade stones	Each	4
23. Top width stones	Do	4
24. Date stone	Do	1
25. Clearing jungle	L. S.	...
Improving the present channel of Siddapur.		
1. Mile stones	Each	3
2. Furlong stones	Do	17
3. Bed grade stones	Do	144
4. Bank grade stones	Do	36
5. Index stones	Do	76
Relieving weir of 14′ long.		
1. Burnt stone in surki mortar	C. ft.	476
2. Do slabs	S. ft.	89
3. Pointing with surki mortar	Sqr.	2·87
4. Earthwork, excavation and benching rock	L. S.	...
Miscellaneous works.		
1. Erecting a shed for the use of subordinate and pay of the temporary meistri	L. S.	...
2. Cost of bringing medicine to coolies	Do	...
3. Survey charges	Do	...

K. PRAHALADA RAO,
Executive Engineer.